

Celtic Concrete Corporation

Po Box 980, Townsend MT,59644

# Estimate

Date	Estimate #
4/5/2021	122

Name / Address
Court House, Townsend, Mt.

Project

Description	Qty	Cost	Total
Concrete Grade out existing rock in walkway area. Form and pour new walkway approx 6' x60 x4" and 7' x10'x4" area in front of building. Pour 7'x10'x4" in rear of building.(existing concrete to be remove by others. Dowel rebar into existing concrete and # 4 rebar @ 24" oc sitting on concrete chairsin walkway. Broom Finsh with one coat of Cure and Seal.		7,500.00	7,500.00
Concrete Celtic will furnish all labor and material to completeabove portion of the project. Celtic will not be responsible for any permits or cracking that occurs in concrete.		0.00	0.00
Sales Tax		9.50%	0.00
		<b>Total</b>	\$7,500.00

Customer Signature \_\_\_\_\_